BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of the Work: Improvements to drains of mainroads of Navyanagara in ward No.07 Byatarayanapura

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	720.50	Earthwork excavation by manual means in rodinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surafce levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications with all lead and left as per directions of engineer in charge of the work.	Cum	137.80	Rupees One Hundred Thirty Seven and Eighty Paise Only
2	76.20	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration inlcuding curing for 14 days including cost of all materials labour, HOM curing, form works, scaffolding and centering complete as per specification with all lead and left as per directions of engineer in charge of the work.	Cum	5421.90	Rupees Five Thousand Four Hundred Twenty One and Ninety Paise Only
3	123.84	Providing and laying Plain/Reinforcement cement concrete M20 with OPC @ 320 kgs with 20mm and down size graded granite metal coarse aggregates @0.69 cum and fine aggregates @ 0.46cum, with super plastisicer @3lts confirming to IS9103-1999 Reaffirmed-2008 in open foundation complete as per drawing andtechincal specifications including cost of all materials, labour HOM curing, form works, scaffolding and centering complete as per specifications with all lead and left as per	Cum	5148.42	Rupees Five Thousand One Hundred Forty Eight and Forty Two Paise Only
4	58.32	Providing and constructing granite /trap/basalt size stone masonry in foundation with cement mortar 1:6, stone hammered dressed in courses not less than 20cms hign, bond stones at two m apart in each course including cost of materials, labour, curing etc., complete as per specifications with all lead and left as per directions of engineer in charge of the work.	Cum	4871.76	Rupees Four Thousand Eight Hundred Seventy One and Seventy Six Paise Only
5	97.20	Providing ruled pointing to coursed stone masonry with cement mortar 1:4, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications cement mortar 1:4. with all lead and left as per directions of engineer in charge of the work.	Sqm	148.40	Rupees One Hundred Forty Eight and Forty Paise Only

6	6.19	Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specificationsTMT Fe500 with all lead and left as per directions of engineer in charge of the work.	(1) MT Sqm	72326.98	Rupees Seventy Two Thousand Three Hundred Twenty Six and Ninety Eight Paise Only
7	900.00	Providing and removing Centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular slabs /side walls polygon in plan including cost of materials, labour complete as per specification and directions of the Engineer in charge	Sqm	483.36	Rupees Four Hundred Eighty Three and Thirty Six Paise Only
8	385.65	Providing and fixing 10cms thick pre cast RCC covering slab using reinforced cement concrete M20 mix with stone aggregate 20mm and down size including centring shuttering reinforcement and bar bending machine mixed concrette laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing complete as per specfications with all lead and left as per directions of engineer in charge of the work.	Sqm	2337.00	Rupees Two Thousand Three Hundred Thirty Seven Only
9	162.00	Providing and fixing 20 cm thick pre cast RCC covering slab using reinforced cement concrete M 20 mix with stone aggregate 20 mm and down size including centring shuttering reinforcement and bar bending machine mixed concrete laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing comlete as per specification with all lead and left as per directions of engineer in charge of the work.	Sqm	5418.00	Rupees Five Thousand Four Hundred Eighteen Only
10	60.00	Laying Reinforced cement concrete pipe NP2 / prestressed concrete pipe for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets complete as per specifications. MORTH Specification No. 2900 B. 1200 mm dia MORTH Specification with all lead and left as per directions of engineer in charge of the work.	(2) RMT Sqm	5976.28	Rupees Five Thousand Nine Hundred Seventy Six and Twenty Eight Paise Only
11	6.75	Providing 100mm and down size nominal size with all lead and left as per directions of engineer in charge of the work.	Nos	987.62	Rupees Nine Hundred Eighty Seven and Sixty Two Paise Only
12	2.26	Providing 40mm and down size nominal size with all lead and left as per directions of engineer in charge of the work.	Sqm	1091.43	Rupees One Thousand Ninety One and Forty Three Paise Only
13	2.26	Providing 20mm and down size nominal size with all lead and left as per directions of engineer in charge of the work.	Nos	1091.43	Rupees One Thousand Ninety One and Forty Three Paise Only

14	1.70	Providing Fine aggrgate 2.36mm nominal size with all lead and left as per directions of engineer in charge of the work.	Cum	1054.29	Rupees One Thousand Fifty Four and Twenty Nine Paise Only
15	30.00	Providing and fixing MS Grating 260x260 mm with all lead and left as per directions of engineer in charge of the work.	Mtr	89.84	Rupees Eighty Nine and Eighty Four Paise Only
16	720.50	Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as as per specification with all lead and left as per directions of engineer in charge of the work.	Cum	94.34	Rupees Ninety Four and Thirty Four Paise Only

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

ಕಂಡಿಕೆ (57) ರಲ್ಲಿ ವಿವರಿಸಿರುವಂತೆ ಅಂಶಗಳ ಬಗ್ಗೆ
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು(BTP) ರವರು
ದೃಢೀಕರಿಸಿಕೊಳ್ಳುವ ಷರತ್ತಿಗೆ ಒಳಪಡಿಸಿ ಟಿ.ಒ.ಸಿ.ಯನ್ನ
ಅನುಮೋದಿಸಿದೆ.
ಕರಡು ಟೆಂಡರ್ ಷೆಡ್ಯೂಲ್‌ನ್ನು ತಿದ್ದುಪಡಿ ಮಾಡದಂತೆ
ತಿದ್ದುಪಡಿ ಇಲ್ಲದೆ ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ.
ತಿದ್ದುಪಡಿಗಳ ಒಟ್ಟು ಸಂಖ್ಯೆ : (13)
ರದ್ದುಗೊಳಿಸಿರುವ ಒಟ್ಟು ಐಟಂಗಳ ಸಂಖ್ಯೆ :
17/07/2020
ಅಭಿಯಂತರರು (ಪೂರ್ಣಪ್ರಭಾವ)